



Rig #2 Inventory
Depth Rating : 7,000'

Drawworks : Ideco Model 5525 H-37 with 15" Double Hydromatic w/crown-o-matic

Power : Detroit Series 60

#1 Pump : Ideco 550 Duplex p/b by Detroit 60 series

#2 Pump : Emsco DB-550 Duplex p/b Detroit 60 Series

Mast : Ideco 103' Hydraulic telescoping, 224,000# hookload

Substructure : Telescoping sub from 11'1" to 12'6" with table and vertical drive clearance 7'10" on rotary beam 9' on rotary table with 200,000# set back

Traveling Equip.: Ideco 165 Ton Shorty's with hook

Rotary Table : Ideco 20 1/2 W/44" center

Generators : 266 KW generator p/b Cummins KT 1150

BOP Equipment : Hydril 11" 3000 PSI Annular, Shaffer 11" 3000 PSI Double Ram Choke 2" 3000# with 4 Station Cameron 80 gallon Closing Unit

Drill Pipe : 6,000' - 16.60 4 1/4" drill pipe

Drill Collars : 4-8" 24-6 1/4"

Mud Systems : 2 steel pit 400 bbl capacity

Solids Control Equipment : Double life, low profile, Double Screen Demco Desander

Rig Houses : 7'6"W x 30'L Top Doughouse, Insulated/

Water Tank : 438 barrel skid mount tank

As of : 2/4/2011